



**ROCKFORD BOARD OF EDUCATION
INVITATION FOR BID ON SUPPLIES, MATERIALS, EQUIPMENT OR SERVICES
FOR SCHOOL DISTRICT NO. 205
ROCKFORD, ILLINOIS**

IFB No. **24-46 Interior & Exterior Door Replacement at Eight Schools**

DATE: **April 4, 2024**

RE: **ADDENDUM NO. 1**

To All Bidders:

Included are modifications, clarifications and/or corrections for the Project Manual and are hereby made a part of the contract documents. Please attach this addendum to the Project Manual(s) in your possession. Please note the receipt of this addendum on the bid form. Bidders shall review changes to all portions of this work as changes to one portion may affect the work of another.

If you plan to hand deliver your IFB submission on the due date, please note you must check in on the 1st floor prior to coming to the bid opening. Please allow time for this as late submission will not be accepted.

Refer all questions relative to the business aspect, Instructions to Bidders, Special Conditions, and questions concerning the technical aspect of the documents to the Director of Purchasing by email at purchasingdeptstaff@rps205.com.

ROCKFORD BOARD OF EDUCATION

By: Dane Youngblood
Director of Purchasing

ADDENDUM ONE

RLJA Project No.: **23-100**
RPS Bid #: **24-46**

Date: **April 4, 2024**

Subject: **CHANGES to the BIDDING DOCUMENTS**

Project: **DOOR AND FRAME REPLACEMENT PROJECT FOR
ROCKFORD PUBLIC SCHOOL DISTRICT #205
ROCKFORD, ILLINOIS**

Bids Due: **2:00PM, THURSDAY, APRIL 25, 2024**


From: **ARCHITECT: RICHARD L. JOHNSON ASSOCIATES, INC.
4703 CHARLES STREET
ROCKFORD, IL 61108**

To: **ALL PROJECT DOCUMENT HOLDERS**

Please reproduce this Addendum as needed and attach to the Project Manuals for the above project.

Bidders shall indicate receipt of this and all Addenda in the space provided on the Bid Form. Failure to do so may be sufficient cause to reject the bid.

Sincerely,
RICHARD L. JOHNSON ASSOCIATES, INC.



Scott R. Johnson, AIA, LEED AP

This Addendum consists of:
Pages 1 thru 2.
Pre-Bid Meeting Minutes - 2 pages.
Pre-Bid Meeting Attendance Record – 1 page.
Pre-Bid Conference Opening Statement – 1 page.
2024-2025 RPS 205 School Year Calendar – 1 page.
RPS 205 Start/Dismissal Time Sheets – 2 pages.
Specification Section 087100 Finish Hardware – 19 pages.

NOTE: Wherein this Addendum conflicts with the original Project Manual and Drawings, this Addendum shall govern.

CHANGES to the PROJECT MANUAL

1. GENERAL ITEMS

- 1.1. See attached Pre-Bid Meeting Notes and attendance record.
- 1.2. See attached 2024-2025 RPS 205 School Year Calendar and RPS 205 Start/Dismissal Time sheets (Times may change).

2. SPECIFICATION SECTION 087100 FINISH HARDWARE

- 2.1. Add Specification Section 087100 Finish Hardware.

CHANGES to the DRAWINGS

3. SHEET A106

- 3.1. Door Schedule – Lathrop: Door LO, change door type to ‘WD’ in lieu of HM.

END ADDENDUM NUMBER 1

PRE-BID MEETING NOTES

RPS No. 24-46

RLJA No. 23-100

RPS #205

Door and Frame Replacement Project

PRE-BID DATE & TIME: Tuesday, April 2, 2024 @ 1:00pm

Items Discussed

1. Meeting Sign-Up Sheet was passed around to attendees and the Pre-Bid Conference Opening Statement was read aloud.
2. Work takes place at eight different schools including Bloom ES, Ellis ES, Fairview EC, Lathrop ES, McIntosh ES, Maria Montessori, Riverdahl ES and Summerdale EC.
3. There will be other renovation projects taking place at the same time in some of the schools over the summer.
4. The materials used on the project are Tax Exempt.
5. Bid RFI Procedure – Email Only – All correspondence MUST be sent to Dane Youngblood, Director of Purchasing via email at purchasingdeptstaff@rps205.com.
6. 5% Bid Security must accompany the Bid.
7. 100% Performance & Payment Bond will be required for the project.
8. The building permit will be obtained by the Owner/Architect thru the Regional Office of Education.
9. The project will be bid out to General Contractors under a Base Bid. There are no Alternate Bids.
10. The schools will be occupied during the Fall of 2024.
11. There are no unit prices for the project.
12. Contractors can tap off the existing building's electrical and water services for construction purposes.
13. General Contractor can use existing toilet facilities at the building for the workers to use.
14. Construction meetings will be held during construction. General Contractor to run the meetings, take meeting notes and distribute.

15. All workers are required to complete the criminal background check. RPS completes the background checks. There is no cost to contractors.
16. The General Contractor needs to have a designated foreman for the project on site as required to properly coordinate the work. One foreman can be used for all schools.
17. Mark the number of addendum you receive on the bid form.
18. Final cleaning on the interior and exterior shall be by the General Contractor.
19. Contractors can contact Megan Simon at 815-378-3632 to coordinate additional site visits.
20. General Contractor shall provide dumpsters as required for the project. Provide plywood under the load points of the dumpster. Coordinate location with the Owner.
21. Prevailing wages are required for this project.
22. The schedule for the project is as follows.:

Board Award	May 21, 2024
Start Construction	June 17, 2024

Contractor shall provide on the bid form the number of calendar days it will take to complete after commencement. All work shall be complete by December 31, 2024.
23. Close out documents will be processed thru the Architect. The Owner requires one electronic copy on a flash drive and one hard copy.
24. Contractor shall coordinate all staging locations with the Owner
25. RPS will not publish budgets for the projects.
26. Submittal process will be thru the software PMWeb.
27. There is a location on the bid form that the contractor shall break out the cost for each school. This needs to be included when you submit your bid.
28. Most schools have activity during the summer.
29. Teachers are back in school August 19, 2024. Students start back August 28, 2024.
30. All drawings were briefly reviewed with the scope of work

END OF MEETING NOTES

24-46 LIFE SAFETY - DOOR REPLACEMENT

SIGN-IN SHEET

**RICHARD L. JOHNSON
ASSOCIATES | ARCHITECTS**

4703 Charles Street • Rockford, IL 61108
815.398.1231 • fax 815.398.1280
www.rljarch.com

NAME	COMPANY	EMAIL
JON DAUCHEN	LARSON + LARSON	THAL@LLBUILDERS.NET
Kari's Belke	FH Paschen	KBelke@FHPaschen.com
Jake Schlichting	DPI Construction	Schlichting19@yahoo.com
Jon Alexander	Stenstrom Construction Group	Jon.a@stenstrom.com
DARRYL BROWN	APR CONSTRUCTION	MONTA@APRCONSTRUCTION.NG DARRYL@APRCONSTRUCTION.NG
MEGAN SIMON	RPS 205	MEGAN.SIMON@RPS205.COM

PRE-BID CONFERENCE OPENING STATEMENT

Welcome to the mandatory pre-bid conference for 24-46 Interior & Exterior Door Replacement at Eight Schools for the Rockford Public Schools.

The purpose of this meeting is to receive input, comments, questions, clarifications and suggested changes relative to this solicitation. As a reminder, the only acceptable changes to the Bid/RFP are formal Addenda published by the RPS Purchasing department. Additionally, the Addendum may address other issues identified by the School District.

The goal of today's meeting is to increase your knowledge of the solicitation as it is written and provide an information mechanism in which you may advise the School District of any changes it should make. Consequently, any changes you wish the Rockford Public Schools to consider must be submitted in writing to the Purchasing department before the deadline as expressed in the solicitation.

We will try to answer as many of the questions as possible. If we cannot answer a question today, we will defer that answer to the published Addendum. Additionally, minutes from this pre-bid conference will be published in the Addendum.

- Bid Opening is scheduled for April 25, 2024 at 2:00 pm Rockford Board of Education, 6th floor Conference Room. Late bids will not be accepted. Faxed or emailed bids will not be accepted.
- Board Approval: May 21, 2024.
- Bid RFI Procedures - All written correspondence during the bid process **MUST** be sent to Dane Youngblood, Director of Purchasing, via email at PurchasingDeptStaff@rps205.com. Last RFI will be accepted until April 16, 2024 at 12:00 pm. Last addendum will be issued by April 18, 2024 at 4:30 pm.
- Addenda will be emailed to all attendees at the pre-bid conference, posted on the RPS website and Bonfire.
- PLEASE reference the **REQUIRED FORMS CHECK LIST** for all documents that **must** be submitted with your bid offer form. All forms must be properly completed, signed and submitted or your bid will be deemed non-responsive.

School Calendar 2024 - 2025

Aug. 14-15 In Person Registration Aug. 26-27 Teacher Institute Aug. 28 K-12 First Day of School Aug. 28 EC Non-program Day Aug. 29 EC First Day of School Sept. 2 Labor Day	August/September 2024							7 EC Non-program Day 17 Presidents Day 21 Teacher Institute	February 2025						
	S	M	T	W	Th	F	S		S	M	T	W	Th	F	S
	25	26	27	28	29	30	31								1
	1	2	3	4	5	6	7		2	3	4	5	6	7	8
	8	9	10	11	12	13	14		9	10	11	12	13	14	15
	15	16	17	18	19	20	21		16	17	18	19	20	21	22
	22	23	24	25	26	27	28		23	24	25	26	27	28	
	29	30													
4 EC Non-program Day 11 Teacher Institute 14 Columbus Day- Observed in School	October 2024							7 End of Trimester Elementary 7 EC Non-Program Day 21 End of Quarter 24-28 Spring Break	March 2025						
	S	M	T	W	Th	F	S		S	M	T	W	Th	F	S
			1	2	3	4	5								1
	6	7	8	9	10	11	12		2	3	4	5	6	7	8
	13	14	15	16	17	18	19		9	10	11	12	13	14	15
	20	21	22	23	24	25	26		16	17	18	19	20	21	22
	27	28	29	30	31				23	24	25	26	27	28	29
									30	31					
1 End of Quarter MS 4 EC Non-Program Day 5 Election Day 11 Veterans Day- Observed In School 22 End of Trimester Elementary 25 Comp Day for Parent Teacher Conference 26 Comp Day for Columbus Day 27 Comp Day for Veterans Day 28-29 Thanksgiving Break	November 2024							18 Good Friday- No School	April 2025						
	S	M	T	W	Th	F	S		S	M	T	W	Th	F	S
						1	2								
	3	4	5	6	7	8	9				1	2	3	4	5
	10	11	12	13	14	15	16		6	7	8	9	10	11	12
	17	18	19	20	21	22	23		13	14	15	16	17	18	19
	24	25	26	27	28	29	30		20	21	22	23	24	25	26
									27	28	29	30			
23-31 Winter Break No School	December 2024							2 EC Non-program Day 16 Last day for seniors 26 Memorial Day	May 2025						
	S	M	T	W	Th	F	S		S	M	T	W	Th	F	S
													1	2	3
	1	2	3	4	5	6	7		4	5	6	7	8	9	10
	8	9	10	11	12	13	14		11	12	13	14	15	16	17
	15	16	17	18	19	20	21		18	19	20	21	22	23	24
	22	23	24	25	26	27	28		25	26	27	28	29	30	31
	29	30	31												
1-3 Winter Break No School 17 End of Quarter/Semester - Secondary 20 - MLK Jr Day No School	January 2025							4 EC Last Day of School 5 K-12 Last Day of School/ EC Non-Program Day 6 Parent Teacher Conferences 9-13 Emergency Days 19 Juneteenth	June 2025						
	S	M	T	W	Th	F	S		S	M	T	W	Th	F	S
				1	2	3	4		1	2	3	4	5	6	7
	5	6	7	8	9	10	11		8	9	10	11	12	13	14
	12	13	14	15	16	17	18		15	16	17	18	19	20	21
	19	20	21	22	23	24	25		22	23	24	25	26	27	28
	26	27	28	29	30	31			29	30					

Elem Trimesters	
1st	60
2nd	57
3rd	57
Total	174

MS Quarters	
1st	46
2nd	39
3rd	42
4th	47
Total	174

HS Semesters	
1st	85
2nd	89
Total	174

KEY	
Holiday Break- No School	
Professional Development- No School	
Early Childhood Non-program Day	
End of Secondary Grading Period	
End of Elementary Grading Period	
End of Grading Period All Grade Levels	
*Emergency Days	

BACK TO SCHOOL

2023-2024 Start/Dismissal Times

Revised 8/25/2023

EARLY CHILDHOOD

Monday – Friday	
Beyer Summerdale *Head Start Collaboration	Full Day Session 9:00 a.m. – 3:20 p.m. 8:45 a.m. – 3:30 p.m.*
	AM Session 9:00 a.m. – 11:35 a.m. 8:45 a.m. – 11:35 a.m.*
	PM Session 12:45 p.m. – 3:20 p.m. 12:40 p.m. – 3:30 p.m.*
Monday – Friday	
Fairview	Full Day Session 7:50 a.m. – 2:10 p.m.
	AM Session 7:50 a.m. – 10:25 a.m.
	PM Session 11:35 a.m. – 2:10 p.m.
Monday – Friday	
Nashold	Full Day Session 8:00 a.m. – 2:15 p.m.
	AM Session 8:00 a.m. – 10:30 a.m.
	PM Session 11:45 a.m. – 2:15 p.m.
Monday – Friday	
Circles of Learning	6:00 a.m. – 5:30 p.m.
Monday – Friday	
Roosevelt	AM Session 8:05 a.m. – 10:40 a.m.
	PM Session 12:00 p.m. – 2:35 p.m.

ELEMENTARY SCHOOLS

Monday – Friday	
Bloom Brookview Carlson Cherry Valley Constance Lane Froberg Hillman Johnson Lathrop McIntosh Riverdahl Washington Welsh West View Whitehead	7:15 a.m. – 2:15 p.m.
Gregory Lewis Lemon Spring Creek	7:35 a.m. – 2:00 p.m.
Ellis	7:45 a.m. – 2:45 p.m.
Rolling Green	8:20 a.m. – 3:20 p.m.

2023-2024 Start/Dismissal Times

Revised 8/25/2023

MIDDLE SCHOOLS

Monday – Wednesday & Friday	
Eisenhower	9:05 a.m. – 4:05 p.m.
Flinn	
Kennedy	Thursday
Lincoln	10:05 a.m. – 4:05 p.m.
RESA	
Monday – Wednesday & Friday	
West	9:05 a.m. – 4:05 p.m.
	8:12 a.m. (zero hour)
	Thursday
	10:05 a.m. – 4:05 p.m.
	9:19 a.m. (zero hour)

SPECIAL PROGRAM SCHOOLS

Monday – Friday	
Barbour	7:15 a.m. – 2:15 p.m.
Conklin	7:35 a.m. – 2:00 p.m.
Haskell	7:20 a.m. – 2:20 p.m.
Marshall Elementary	8:20 a.m. – 3:20 p.m.
Montessori	9:00 a.m. – 3:25 p.m.
Monday – Wednesday & Friday	
Marshall Middle	9:05 a.m. – 4:05 p.m.
	Thursday
	10:05 a.m. – 4:05 p.m.

HIGH SCHOOLS

Monday – Wednesday & Friday	
East Jefferson	8:10 a.m. – 3:25 p.m.
	Thursday
Auburn	9:10 a.m. – 3:25 p.m.
	Monday – Wednesday & Friday
	8:10 a.m. – 3:25 p.m.
	7:15 a.m. (zero hour)
	Thursday
Guilford	9:10 a.m. – 3:25 p.m.
	8:15 a.m. (zero hour)
	Monday – Wednesday & Friday
	8:10 a.m. – 3:25 p.m.
	7:15 a.m. (zero hour)
	Thursday
	9:10 a.m. – 3:25 p.m.
	8:22 a.m. (zero hour)

ROOSEVELT

Monday – Friday	
Full Day	8:00 a.m. – 2:20 p.m.
AM Session	8:00 a.m. – 10:30 a.m.
PM Session	11:50 a.m. – 2:20 p.m.

DIVISION 08 – OPENINGS
SECTION 087100
FINISH HARDWARE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Mechanical door hardware for interior and exterior swinging doors.
- B. Related Requirements:
 - 1. Section 081113 "Hollow Metal Doors and Frames" for new hollow metal doors set in new hollow metal frames.
 - 2. Section 081416 "Flush Wood Doors" for new wood doors set in new hollow metal frames.
 - 3. Section 084113 "Aluminum Framed Entrance" for new aluminum doors set in new aluminum frames.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include construction and installation details, material descriptions, dimensions of individual components and profiles, and finishes.
- B. Other Action Submittals:
 - 1. Door Hardware Schedule: Prepared by or under the supervision of Installer, detailing fabrication and assembly of door hardware, as well as installation procedures and diagrams. Coordinate final door hardware schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of door hardware.
 - a. Submittal Sequence: Submit door hardware schedule concurrent with submissions of Product Data, Samples, and Shop Drawings. Coordinate submission of door hardware schedule with scheduling requirements of other work to facilitate the fabrication of other work that is critical in Project construction schedule.
 - b. Format: Comply with scheduling sequence and vertical format in DHI's "Sequence and Format for the Hardware Schedule." Double space entries, and number and date each page.

- c. Content: Include the following information:
 - 1) Identification number, location, hand, size, and material of each door and frame.
 - 2) Locations of each door hardware set, cross-referenced to Drawings on floor plans and to door and frame schedule.
 - 3) Complete designations, including name and manufacturer, type, style, function, size, quantity, function, and finish of each door hardware product.
 - 4) Fastenings and other pertinent information.
 - 5) Explanation of abbreviations, symbols, and codes contained in schedule.
 - 6) Mounting locations for door hardware.
 - 7) List of related door devices specified in other Sections for each door and frame.
- 2. Keying: Provide Sargent LA at Bloom Elementary, Ellis Elementary, McIntosh Elementary, Montessori at Marsh Elementary. Provide Sargent LJ at Fairview ECC. Provide Sargent RA at Lathrop Elementary. Provide Schlage F at Riverdahl Elementary. Provide Yale GB at Summerdale ECC. Prepared by or under the supervision of Installer, detailing Owner's final keying instructions for locks. Include schematic keying diagram and index each key set to unique door designations that are coordinated with the Contract Documents. Coordinate all keying with the Owner.

1.4 INFORMATIONAL SUBMITTALS

- A. Warranty: Special warranty specified in this Section.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Supplier of products and an employer of workers trained and approved by product manufacturers and an Architectural Hardware Consultant who is available during the course of the Work to consult with Contractor, Architect, and Owner about door hardware and keying.
 - 1. Warehousing Facilities: In Project's vicinity.
 - 2. Scheduling Responsibility: Preparation of door hardware and keying schedules.
- B. Source Limitations: Obtain each type of door hardware from a single manufacturer.
- C. Means of Egress Doors: Latches do not require more than 15 lbf (67 N) to release the latch. Locks do not require use of a key, tool, or special knowledge for operation.
- D. Accessibility Requirements: Comply with applicable provisions in the DOJ's 2010 ADA Standards for Accessible Design and ICC A117.1.
 - 1. Provide operating devices that do not require tight grasping, pinching, or twisting of the wrist and that operate with a force of not more than 5 lbf (22.2 N).
 - 2. Bevel raised thresholds with a slope of not more than 1:2. Provide thresholds not more than 1/2 inch (13 mm) high.

3. Closers: Adjust door and gate closer sweep periods so that, from an open position of 90 degrees, the time required to move the door to a position of 12 degrees from the latch is 5 seconds minimum.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Inventory door hardware on receipt and provide secure lock-up for door hardware delivered to Project site.
- B. Tag each item or package separately with identification coordinated with the final door hardware schedule, and include installation instructions, templates, and necessary fasteners with each item or package.
- C. Deliver keys to manufacturer of key control system for subsequent delivery to Owner.

1.7 COORDINATION

- A. Installation Templates: Distribute for doors, frames, and other work specified to be factory prepared. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing door hardware to comply with indicated requirements.
- B. Security: Coordinate installation of door hardware, keying, and access control with Owner's security consultant.
- C. Existing Openings: Where hardware components are scheduled for application to existing construction or where modifications to existing door hardware are required, field verify existing conditions and coordinate installation of door hardware to suit opening conditions and to provide proper door operation.

1.8 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of door hardware that fail in materials or workmanship within specified warranty period.
 1. Failures include, but are not limited to, the following:
 - a. Structural failures including excessive deflection, cracking, or breakage.
 - b. Faulty operation of doors and door hardware.
 - c. Deterioration of metals, metal finishes, and other materials beyond normal weathering and use.
 2. Warranty Period: Two years from date of Substantial Completion, unless otherwise indicated.
 - a. Exit Devices: 3 years from date of Substantial Completion.
 - b. Manual Closers: 10 years from date of Substantial Completion.
 - c. Bored Locksets: 3 years from date of Substantial Completion.

- d. Hinges: Life of Building from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SCHEDULED DOOR HARDWARE

- A. Provide door hardware for each door as scheduled in Part 3 "Door Hardware Schedule" Article to comply with requirements in this Section as follows:
 - 1. Continuous Hinges: Roton, No substitutions.
 - 2. Locksets: Schlage, No substitutions.
 - 3. Exit Devices: Sargent, No substitutions.
 - 4. Closers: Norton, No substitutions.
 - 5. All Other Hardware: As specified or Owner approved equal.

2.2 FABRICATION

- A. Manufacturer's Nameplate: Do not provide products that have manufacturer's name or trade name displayed in a visible location except as otherwise approved by Architect.
 - 1. Manufacturer's identification is permitted on rim of lock cylinders only.
- B. Base Metals: Produce door hardware units of base metal indicated, fabricated by forming method indicated, using manufacturer's standard metal alloy, composition, temper, and hardness. Furnish metals of a quality equal to or greater than that of specified door hardware units and BHMA A156.18.
- C. Fasteners: Provide door hardware manufactured to comply with published templates prepared for machine, wood, and sheet metal screws. Provide screws that comply with commercially recognized industry standards for application intended, except aluminum fasteners are not permitted. Provide Phillips flat-head screws with finished heads to match surface of door hardware, unless otherwise indicated.
 - 1. Concealed Fasteners: For door hardware units that are exposed when door is closed, except for units already specified with concealed fasteners. Do not use through bolts for installation where bolt head or nut on opposite face is exposed unless it is the only means of securely attaching the door hardware. Where through bolts are used on hollow door and frame construction, provide sleeves for each through bolt.
 - 2. Spacers or Sex Bolts: For through bolting of hollow-metal doors and wood doors.
 - 3. Gasketing Fasteners: Provide noncorrosive fasteners for exterior applications and elsewhere as indicated.

2.3 FINISHES

- A. Provide finishes complying with BHMA A156.18 as indicated in door hardware schedule.

- B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- C. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine doors and frames, with Installer present, for compliance with requirements for installation tolerances, labeled fire-rated door assembly construction, wall and floor construction, and other conditions affecting performance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Steel Doors and Frames: For surface applied door hardware, drill and tap doors and frames according to ANSI/SDI A250.6.

3.3 INSTALLATION

- A. Mounting Heights: Mount door hardware units at heights to comply with the following unless otherwise indicated or required to comply with governing regulations.
 - 1. Standard Steel Doors and Frames: ANSI/SDI A250.8.
- B. Install each door hardware item to comply with manufacturer's written instructions. Where cutting and fitting are required to install door hardware onto or into surfaces that are later to be painted or finished in another way, coordinate removal, storage, and reinstallation of surface protective trim units with finishing. Do not install surface-mounted items until finishes have been completed on substrates involved.
 - 1. Set units level, plumb, and true to line and location. Adjust and reinforce attachment substrates as necessary for proper installation and operation.
 - 2. Drill and countersink units that are not factory prepared for anchorage fasteners. Space fasteners and anchors according to industry standards.
- C. Hinges: Install type quantities indicated in door hardware schedule.
- D. Thresholds: Set threshold in full bed of sealant.
- E. Perimeter Gasketing: Apply to head and jamb, forming seal between door and frame.
- F. Door Bottoms: Apply to bottom of door, forming seal with threshold when door is closed.

- G. Closers: Sex-bolt all closers on wood doors. Provide drop plates where required.

3.4 ADJUSTING

- A. Initial Adjustment: Adjust and check each operating item of door hardware and each door to ensure proper operation or function of every unit. Replace units that cannot be adjusted to operate as intended. Adjust door control devices to compensate for final operation of heating and ventilating equipment and to comply with referenced accessibility requirements.
1. Door Closers: Adjust sweep period to comply with accessibility requirements and requirements of authorities having jurisdiction.

3.5 CLEANING AND PROTECTION

- A. Clean adjacent surfaces soiled by door hardware installation.
- B. Clean operating items as necessary to restore proper function and finish.
- C. Provide final protection and maintain conditions that ensure that door hardware is without damage or deterioration at time of Substantial Completion.

3.6 DOOR HARDWARE SCHEDULE

Hardware Group No. 01

BGYM1 BGYM2

Provide each PR door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
2	EA	ROTON HINGE	780-112HD	CLR	ROT
1	EA	REMOVABLE MULLION	L980S	689	SAR
2	EA	FIRE EXIT DEVICE	12-8813-ETL	626	SAR
1	EA	MORTISE CYLINDER	MANUFACTURER & KEYWAY TBD BY SCHOOL - REFER TO SPEC	626	TBD
2	EA	RIM CYLINDER	MANUFACTURER & KEYWAY TBD BY SCHOOL - REFER TO SPEC	626	TBD
2	EA	OH STOP	100S	630	GLY
2	EA	CLOSER	PR7500	689	NOR
2	EA	KICK PLATE	8400 10" X 1" LDW B-CS	630	IVE
1	EA	GASKETING	188SBK PSA	BK	ZER
1	EA	MEETING STILE	328AA-S	AA	ZER

Hardware Group No. 02

BPE

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5 NRP	652	IVE
1	EA	CLASSROOM LOCK	ALX70P6 RHO	626	SCH
1	EA	CLOSER	PR7500	689	NOR
1	EA	KICK PLATE	8400 10" X 2" LDW B-CS	630	IVE
1	EA	WALL STOP	WS406/407CCV	630	IVE
1	EA	GASKETING	188SBK PSA	BK	ZER

Hardware Group No. 03

B1 B100 BLIB BPTO FJ3 FK1
 ROP2 RWRK

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	CLASSROOM LOCK	ALX70P6 RHO	626	SCH

NOTE: REFER TO DEMOLITION NOTE (A) AND KEYNOTE (1) ON PLANS.

PROVIDE ANY AND ALL PLATES REQUIRED TO COVER/BLANK EXISTING UNUSED DOOR AND FRAME PREPS. FIELD VERIFY ALL EXISTING OPENINGS TO CONFIRM FUNCTIONALITY OF NEW HARDWARE ITEMS:

- 4"W X +/-24"H PUSH PLATES – BOTH SIDES OF DOOR TO COVER HOLES FROM DEMOED HARDWARE.
- EDGE FILLER PLATE FROM DEMOED YALE 350 MORTISE LOCK.
- STRIKE FILLER PLATE FROM DEMOED YALE 350 MORTISE LOCK.

BALANCE OF EXISTING HARDWARE TO REMAIN.

Hardware Group No. 04

EF

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	ROTON HINGE	780-112HD	CLR	ROT
1	EA	STOREROOM LOCK	ALX80P6 RHO	626	SCH
1	EA	ELECTRIC STRIKE	1500	630	HES
1	EA	CLOSER	CPS7500	689	NOR
1	EA	KICK PLATE	8400 10" X 2" LDW B-CS	630	IVE
1	EA	RAIN DRIP	142AA	AA	ZER
1	SET	GASKETING	328AA-S JAMB SEAL SET	AA	ZER
1	EA	GASKETING	429AA HEAD SEAL	AA	ZER
			MOUNT PRIOR TO ANY HEAD		
			MOUNTED HARDWARE		
1	EA	DOOR SWEEP	39A	A	ZER
1	EA	THRESHOLD	566A-V3-223	A	ZER
1	EA	DOOR CONTACT	BY CONTRACTOR		B/O
1	EA	REQUEST-TO-EXIT SENSOR	BY CONTRACTOR		B/O

CREDENTIAL READER IS TO RELEASE ELECTRIC STRIKE AND SHUNT ANY ALARM ASSOCIATED WITH THE DOOR CONTACT ALLOWING THE DOOR TO BE OPENED.
FREE EGRESS IS ALWAYS AVAILABLE.

ITEMS TO BE PROVIDED BY CONTRACTOR:

REINSTALL EXISTING CREDENTIAL READER ONTO NEW FRAME.

REINSTALL EXISTING DOORBELL BUTTON ONTO NEW FRAME.

DOOR CONTACT.

REQUEST-TO-EXIT SENSOR.

REQUIRED WIRING FROM POWER SUPPLY TO ELECTRIC STRIKE.

REQUIRED POWER AND WIRING TO THE DOORBELL BUTTON.

REQUIRED POWER AND WIRING TO THE DOOR CONTACT.

REQUIRED POWER AND WIRING TO THE REQUEST-TO-EXIT SENSOR.

Hardware Group No. 05

FA1	FA2	FA3	FF1	FF2	FJ1
FJ2	FL1	FN1	FN2	FP1	FP2
FP3	FS1	FS2	FS3	FS4	FS5
FS6	FS7	FS8	FS9	FS10	FT1
FT2					

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	CLASSROOM LOCK	ALX70P6 RHO	626	SCH
1	EA	CONVERSION PLATE	CV-2414 SARGENT		DON

PROVIDE ANY AND ALL PLATES REQUIRED TO COVER/BLANK EXISTING UNUSED DOOR AND FRAME PREPS. FIELD VERIFY ALL EXISTING OPENINGS TO CONFIRM FUNCTIONALITY OF NEW HARDWARE ITEMS:

REMOVE EXISTING MORTISE LOCK AND REPLACE WITH CYLINDRICAL. BALANCE OF EXISTING HARDWARE TO REMAIN.

Hardware Group No. 06

FH1

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	CLASSROOM LOCK	ALX70P6 RHO	626	SCH

NOTE: REFER TO DEMOLITION NOTE (H) AND KEYNOTE (12) ON PLANS.

PROVIDE ANY AND ALL PLATES REQUIRED TO COVER/BLANK EXISTING UNUSED DOOR AND FRAME PREPS. FIELD VERIFY ALL EXISTING OPENINGS TO CONFIRM FUNCTIONALITY OF NEW HARDWARE ITEMS:

- 4"W X +/-24"H PUSH PLATES – BOTH SIDES OF DOOR TO COVER HOLES FROM DEMOED HARDWARE.

BALANCE OF EXISTING HARDWARE TO REMAIN.

Hardware Group No. 07

FB

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	ROTON HINGE	780-112HD	CLR	ROT
1	EA	PANIC HARDWARE	LD-8810	626	SAR
1	EA	CLOSER	CPS7500	689	NOR
1	EA	KICK PLATE	8400 10" X 2" LDW B-CS	630	IVE
1	SET	GASKETING	328AA-S JAMB SEAL SET	AA	ZER
1	EA	GASKETING	429AA HEAD SEAL	AA	ZER
			MOUNT PRIOR TO ANY HEAD MOUNTED HARDWARE		
1	EA	DOOR SWEEP	39A	A	ZER
1	EA	THRESHOLD WITH BUMP STOP	813 x 700E	AA	NGP
1	EA	DOOR CONTACT	BY CONTRACTOR		B/O

NOTE: THRESHOLD TO ALSO COVER GAPS IN FLOORING – NOTCH AROUND NEW FRAMING AS REQUIRED.

ITEMS TO BE PROVIDED BY CONTRACTOR:

DOOR CONTACT.

REQUIRED POWER AND WIRING TO THE DOOR CONTACT.

Hardware Group No. 08

FBLR

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5	652	IVE
1	EA	CLASSROOM LOCK	ALX70P6 RHO	626	SCH
1	EA	OH STOP	100S	630	GLY
1	EA	CLOSER	PR7500	689	NOR
1	EA	KICK PLATE	8400 10" X 2" LDW B-CS	630	IVE
1	EA	GASKETING	188SBK PSA	BK	ZER

Hardware Group No. 09

FC

FH

Provide each PR door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	ROTON HINGE	780-112HD	CLR	ROT
1	EA	ROTON HINGE	780-112HD-EPT10	CLR	ROT
1	EA	POWER TRANSFER	EPT10	689	VON
1	EA	REMOVABLE MULLION	L980S	689	SAR
1	EA	ELECTRIFIED PANIC HARDWARE	56-8810	626	SAR
1	EA	PANIC HARDWARE	LD-8810	626	SAR
1	EA	MORTISE CYLINDER	MANUFACTURER & KEYWAY TBD BY SCHOOL - REFER TO SPEC	626	TBD
2	EA	90 DEG OFFSET PULL	8190EZHD 10" O	630-316	IVE
2	EA	OH STOP	100S	630	GLY
2	EA	CLOSER	CPS7500 X BLADE STOP SPACER X PA MOUNTING PLATE	689	NOR
1	SET	MEETING STILE	8193AA-S	AA	ZER
1	EA	WEATHER STRIPPING	BY DOOR/FRAME MANUFACTURER		B/O
2	EA	DOOR SWEEP	39A	A	ZER
1	EA	THRESHOLD WITH BUMP STOP	813 x 700E	AA	NGP
1	EA	POWER SUPPLY	3500 AS REQ.		SAR
2	EA	DOOR CONTACT	BY CONTRACTOR		B/O
1	EA	REQUEST-TO-EXIT SENSOR	BY CONTRACTOR		B/O

CREDENTIAL READER IS TO RETRACT LATCH AND SHUNT ANY ALARM ASSOCIATED WITH THE DOOR CONTACT(S) ALLOWING THE DOOR TO BE OPENED. FREE EGRESS IS ALWAYS AVAILABLE.

NOTE: THRESHOLD TO ALSO COVER GAPS IN FLOORING – NOTCH AROUND NEW FRAMING AS REQUIRED.

ITEMS TO BE PROVIDED BY CONTRACTOR:

REINSTALL EXISTING CREDENTIAL READER ONTO NEW FRAME.

DOOR CONTACTS.

REQUEST-TO-EXIT SENSOR.

REQUIRED WIRING FROM POWER SUPPLY TO ELECTRIFIED EXIT DEVICE.

REQUIRED POWER AND WIRING TO THE DOOR CONTACTS.

REQUIRED POWER AND WIRING TO THE REQUEST-TO-EXIT SENSOR.

Hardware Group No. 10

FC1

Provide each PR door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
6	EA	HINGE	5BB1 4.5 X 4.5	652	IVE
2	EA	FIRE EXIT DEVICE	12-NB-8715-ETL	626	SAR
2	EA	OH STOP	90SE	630	GLY
			PUSH SIDE TEMPLATE FOR MAX DEGREE		
2	EA	FIRE/LIFE CLOSER	4040SE DE 24V/120V AC/DC AS REQ	689	LCN
			PULL SIDE TEMPLATED FOR MAX DEGREE		
2	EA	KICK PLATE	8400 10" X 2" LDW B-CS	630	IVE
1	EA	GASKETING	188SBK PSA	BK	ZER
1	EA	OVERLAPPING ASTRAGAL	322A	A	ZER

ITEMS TO BE PROVIDED BY CONTRACTOR:

TIE NEW CLOSERS INTO EXISTING FIRE ALARM SYSTEM AS REQUIRED.

Hardware Group No. 11

FD LH

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	ROTON HINGE	780-112HD-EPT10	CLR	ROT
1	EA	POWER TRANSFER	EPT10	689	VON
1	EA	ELECTRIFIED PANIC HARDWARE	56-8810-ETL	626	SAR
1	EA	CLOSER	CPS7500	689	NOR
1	EA	KICK PLATE	8400 10" X 2" LDW B-CS	630	IVE
1	SET	GASKETING	328AA-S JAMB SEAL SET	AA	ZER
1	EA	GASKETING	429AA HEAD SEAL MOUNT PRIOR TO ANY HEAD MOUNTED HARDWARE	AA	ZER
1	EA	DOOR SWEEP	39A	A	ZER
1	EA	THRESHOLD	566A-V3-223	A	ZER
1	EA	DOOR CONTACT	BY CONTRACTOR		B/O
1	EA	POWER SUPPLY	3500 AS REQ.		SAR

CREDENTIAL READER IS TO RETRACT LATCH AND SHUNT ANY ALARM ASSOCIATED WITH THE DOOR CONTACT ALLOWING THE DOOR TO BE OPENED. FREE EGRESS IS ALWAYS AVAILABLE.

ITEMS TO BE PROVIDED BY CONTRACTOR:

REINSTALL EXISTING CREDENTIAL READER ONTO NEW FRAME.

REINSTALL EXISTING REQUEST-TO-EXIT SENSOR ONTO NEW FRAME.
DOOR CONTACT.

REQUIRED WIRING FROM POWER SUPPLY TO ELECTRIFIED EXIT DEVICE.

REQUIRED POWER AND WIRING TO THE DOOR CONTACT.

REQUIRED POWER AND WIRING TO THE REQUEST-TO-EXIT SENSOR.

Hardware Group No. 12

FF FG

Provide each PR door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	ROTON HINGE	780-112HD	CLR	ROT
1	EA	ROTON HINGE	780-112HD-EPT10	CLR	ROT
1	EA	POWER TRANSFER	EPT10	689	VON
1	EA	REMOVABLE MULLION	L980S	689	SAR
1	EA	ELECTRIFIED PANIC HARDWARE	56-8810	626	SAR
1	EA	PANIC HARDWARE	LD-8810	626	SAR
1	EA	MORTISE CYLINDER	MANUFACTURER & KEYWAY TBD BY SCHOOL - REFER TO SPEC	626	TBD
2	EA	90 DEG OFFSET PULL	8190EZHD 10" O	630-316	IVE
2	EA	OH STOP	100S	630	GLY
2	EA	CLOSER	CPS7500 X BLADE STOP SPACER X PA MOUNTING PLATE	689	NOR
1	SET	MEETING STILE	8193AA-S	AA	ZER
1	EA	WEATHER STRIPPING	BY DOOR/FRAME MANUFACTURER		B/O
2	EA	DOOR SWEEP	39A	A	ZER
1	EA	THRESHOLD WITH BUMP STOP	813 x 700E	AA	NGP
1	EA	POWER SUPPLY	3500 AS REQ.		SAR

CREDENTIAL READER IS TO RETRACT LATCH AND SHUNT ANY ALARM ASSOCIATED WITH THE DOOR CONTACTS ALLOWING THE DOOR TO BE OPENED. FREE EGRESS IS ALWAYS AVAILABLE.

NOTE: THRESHOLD TO ALSO COVER GAPS IN FLOORING – NOTCH AROUND NEW FRAMING AS REQUIRED.

ITEMS TO BE PROVIDED BY CONTRACTOR:

REINSTALL EXISTING CREDENTIAL READER ONTO NEW FRAME.

REINSTALL EXISTING REQUEST-TO-EXIT SENSOR ONTO NEW FRAME.

DOOR CONTACTS.

REQUIRED WIRING FROM POWER SUPPLY TO ELECTRIFIED EXIT DEVICE.

REQUIRED POWER AND WIRING TO THE DOOR CONTACTS.

REQUIRED POWER AND WIRING TO THE REQUEST-TO-EXIT SENSOR.

Hardware Group No. 13

FG1 FG4

Provide each PR door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
2	EA	ROTON HINGE	780-112HD	CLR	ROT
1	EA	REMOVABLE MULLION	L980S	689	SAR
2	EA	FIRE EXIT DEVICE	12-8813-ETL	626	SAR
1	EA	MORTISE CYLINDER	MANUFACTURER & KEYWAY TBD BY SCHOOL - REFER TO SPEC	626	TBD
2	EA	RIM CYLINDER	MANUFACTURER & KEYWAY TBD BY SCHOOL - REFER TO SPEC	626	TBD
2	EA	OH STOP	100S	630	GLY
2	EA	CLOSER	PR7500	689	NOR
2	EA	KICK PLATE	8400 10" X 1" LDW B-CS	630	IVE
1	EA	GASKETING	188SBK PSA	BK	ZER
1	EA	MEETING STILE	328AA-S	AA	ZER

Hardware Group No. 14

FG2 FG3

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	ROTON HINGE	780-112HD	CLR	ROT
1	EA	FIRE EXIT DEVICE	12-8813-ETL	626	SAR
1	EA	RIM CYLINDER	MANUFACTURER & KEYWAY TBD BY SCHOOL - REFER TO SPEC	626	TBD
1	EA	OH STOP	100S	630	GLY
1	EA	CLOSER	PR7500	689	NOR
1	EA	KICK PLATE	8400 10" X 2" LDW B-CS	630	IVE
1	EA	GASKETING	188SBK PSA	BK	ZER

Hardware Group No. 15

FIT

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5	652	IVE
1	EA	CLASSROOM LOCK	ALX70P6 RHO	626	SCH
1	EA	CLOSER	PR7500	689	NOR
1	EA	KICK PLATE	8400 10" X 2" LDW B-CS	630	IVE
1	EA	WALL STOP	WS406/407CCV	630	IVE
1	EA	GASKETING	188SBK PSA	BK	ZER

Hardware Group No. 16

LO MMO

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5 NRP	652	IVE
1	EA	CLASSROOM LOCK	ALX70P6 RHO	626	SCH
1	EA	ELECTRIC STRIKE	1500	630	HES
1	EA	OH STOP	100S	630	GLY
1	EA	CLOSER	PR7500	689	NOR
1	EA	KICK PLATE	8400 10" X 2" LDW B-CS	630	IVE
1	EA	GASKETING	188SBK PSA	BK	ZER

CREDENTIAL READER IS TO RELEASE ELECTRIC STRIKE ALLOWING THE DOOR TO BE OPENED. KEYED EGRESS IS AVAILABLE. FREE EGRESS IS ALWAYS AVAILABLE.

ITEMS TO BE PROVIDED BY CONTRACTOR:

REINSTALL EXISTING CREDENTIAL READER ONTO NEW FRAME.

REQUIRED WIRING FROM POWER SUPPLY TO ELECTRIC STRIKE.

Hardware Group No. 17

MCPE

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
3	EA	HINGE	5BB1 4.5 X 4.5	652	IVE
1	EA	CLASSROOM LOCK	ALX70P6 RHO	626	SCH
1	EA	CLOSER	PR7500	689	NOR
1	EA	KICK PLATE	8400 10" X 2" LDW B-CS	630	IVE
1	EA	WALL STOP	WS406/407CCV	630	IVE
1	EA	GASKETING	188SBK PSA	BK	ZER

Hardware Group No. 18

MCQ

Provide each PR door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	ROTON HINGE	780-112HD ACTIVE	CLR	ROT
1	EA	ROTON HINGE	780-112HD-EPT10 INACTIVE	CLR	ROT
1	EA	POWER TRANSFER	EPT10	689	VON
2	EA	FLUSH BOLT (T&B)	FB458 12"	630	IVE
1	EA	DUST PROOF STRIKE	DP2	626	IVE
1	EA	CLASSROOM LOCK	ALX70P6 RHO	626	SCH
1	EA	ELECTRIC STRIKE	1500	630	HES
1	EA	COORDINATOR	COR X FL X MB - AS REQ.	628	IVE
2	EA	CLOSER	CPS7500	689	NOR
2	EA	KICK PLATE	8400 10" X 1" LDW B-CS	630	IVE
1	EA	OVERLAPPING ASTRAGAL	322A	A	ZER
1	SET	GASKETING	328AA-S JAMB SEAL SET	AA	ZER
1	EA	GASKETING	429AA HEAD SEAL MOUNT PRIOR TO ANY HEAD MOUNTED HARDWARE	AA	ZER
1	EA	ASTRAGAL	306-AST - NOTCHED FOR ELECTRIC STRIKE	630	ROC
2	EA	DOOR SWEEP	39A	A	ZER
1	EA	THRESHOLD	566A-V3-223	A	ZER
2	EA	DOOR CONTACT	BY CONTRACTOR		B/O
1	EA	REQUEST-TO-EXIT SENSOR	BY CONTRACTOR		B/O

CREDENTIAL READER IS TO RELEASE ELECTRIC STRIKE AND SHUNT ANY ALARM ASSOCIATED WITH THE DOOR CONTACT ALLOWING THE DOOR TO BE OPENED. KEYED EGRESS IS AVAILABLE. FREE EGRESS IS ALWAYS AVAILABLE.

ITEMS TO BE PROVIDED BY CONTRACTOR:

REINSTALL EXISTING CREDENTIAL READER ONTO NEW FRAME.

DOOR CONTACTS.

REQUEST-TO-EXIT SENSOR.

REQUIRED POWER AND WIRING TO THE DOOR CONTACTS.

REQUIRED WIRING FROM POWER SUPPLY TO ELECTRIC STRIKE.

REQUIRED POWER AND WIRING TO THE REQUEST-TO-EXIT SENSOR.

Hardware Group No. 19

MMS

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	REMOVABLE MULLION	L980S	689	SAR
2	EA	FIRE EXIT DEVICE	12-8815-ETL	626	SAR
1	EA	MORTISE CYLINDER	MANUFACTURER & KEYWAY TBD BY SCHOOL - REFER TO SPEC	626	TBD
1	EA	GASKETING	188SBK PSA	BK	ZER
1	EA	MEETING STILE	328AA-S	AA	ZER

NOTE: REFER TO DEMOLITION NOTE (S) AND KEYNOTES (16 & 17) ON PLANS.

- 3 1/2"W X 15"H PUSH PLATE(S) – EXTERIOR SIDE TO MATCH INTERIOR.
- MODIFY PUSH PLATES AS REQUIRED TO RECEIVE NEW EXIT DEVICES.

BALANCE OF HARDWARE TO REMAIN.

NOTE: FIELD VERIFY EXISTING CONDITIONS FOR INSTALLATION OF NEW HARDWARE ON EXISTING FIRE RATED OPENING PRIOR TO BIDDING OR ORDERING MATERIAL.

NOTE: PROVIDE RIV NUT TYPE FASTENERS WHERE PROPER REINFORCEMENT IN EXISTING FRAME IS NOT PRESENT.

Hardware Group No. 20

RBSMT

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	FIRE EXIT DEVICE	12-8815-ETL	626	SAR

NOTE: REFER TO DEMOLITION NOTE (H) AND KEYNOTES (16) ON PLANS.

- 3 1/2"W X 15"H PUSH PLATE(S) – BOTH SIDES.
- MODIFY PUSH PLATES AS REQUIRED TO RECEIVE NEW EXIT DEVICES.

BALANCE OF HARDWARE TO REMAIN.

NOTE: FIELD VERIFY EXISTING CONDITIONS FOR INSTALLATION OF NEW HARDWARE ON EXISTING FIRE RATED OPENING PRIOR TO BIDDING OR ORDERING MATERIAL.

NOTE: PROVIDE RIV NUT TYPE FASTENERS WHERE PROPER REINFORCEMENT IN EXISTING FRAME IS NOT PRESENT.

Hardware Group No. 21

SBLR

Provide each PR door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
2	EA	ROTON HINGE	780-112HD	CLR	ROT
2	EA	FLUSH BOLT (T&B)	FB458 12"	630	IVE
1	EA	DUST PROOF STRIKE	DP2	626	IVE
1	EA	CLASSROOM LOCK	ALX70P6 RHO	626	SCH
1	EA	COORDINATOR	COR X FL X MB - AS REQ.	628	IVE
2	EA	CLOSER	CPS7500	689	NOR
2	EA	KICK PLATE	8400 10" X 1" LDW B-CS	630	IVE
1	EA	OVERLAPPING ASTRAGAL	322A	A	ZER
1	SET	GASKETING	328AA-S JAMB SEAL SET	AA	ZER
1	EA	GASKETING	429AA HEAD SEAL	AA	ZER
			MOUNT PRIOR TO ANY HEAD MOUNTED HARDWARE		
1	EA	ASTRAGAL	306-AST- NOTCHED FOR ELECTRIC STRIKE	630	ROC
2	EA	DOOR SWEEP	39A	A	ZER
1	EA	THRESHOLD	566A-V3-223	A	ZER
2	EA	DOOR CONTACT	BY CONTRACTOR		B/O
1	EA	REQUEST-TO-EXIT SENSOR	BY CONTRACTOR		B/O

ITEMS TO BE PROVIDED BY CONTRACTOR:

DOOR CONTACTS.

REQUEST-TO-EXIT SENSOR.

REQUIRED POWER AND WIRING TO THE DOOR CONTACTS.

REQUIRED POWER AND WIRING TO THE REQUEST-TO-EXIT SENSOR.

END OF SECTION 087100